



15-039-2 0200-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 8 - 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-8-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Huff Well No. E-1

Location: CNE-SE Sec. 17 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3403' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent