

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-009-24786 -00-00

LEASE NAME Nettleingham-Holland Unit

WELL NUMBER #24-1

NOTICE: Fill out **completely** 1230 Ft. from S Section Line

and return to Cons. Div. 3860 Ft. from E Section Line

office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 24 TWP16 RGE. 14 W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Barton

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 2/24/04

Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 2/24/04

Plugging Completed 2/24/04

The plugging proposal was approved on 2/24/04 (date)

by David Wann w/KCC in Hays, KS (KCC District Agent's Name).

Is ACO-1 filed? Yes (Included) If not, is well log attached? _____

Producing Formation LKC, Arbuckle Depth to Top _____ Bottom _____ TD3508 Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	409	8 5/8	409	0
	Production	None				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well as follows:

2/24: Log tech logged hole from 9:30pm 2/23/04 to 2:30am 2/24/04. LTD 3508. Started plugging hole @ 6:00am 2/24/04 using 60/40 poz, 6% gel as follows @ 3425' w/25 sacks, 935' w/40 sx, 450' w/ 70 sx, 40' w/ 10 sx, RH w/ 15sx, MH w/10 sx. 2/25 : Allied finished plugging hole @ 9:15am 2/24/04. Orders David Wann w/KCC in Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of March, 2004

Notary Public - Kristin Grady
Kristin Grady
My Commission Expires: 2/06/08

Form CP-4

Revised 05-88



RECEIVED
MAR 30 2004
KCC WICHITA