

MAR 19 2004

API NUMBER 15-051-22754-00-00

LEASE NAME Christina

WELL NUMBER 5

1980 Ft. from ^N Section Line

1980 Ft. from ^E Section Line

SEC. 15 TWP. 14S RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 12-19-81

Plugging Commenced 2-9-04

Plugging Completed 2-9-04

MAR 03 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Berexco, Inc. SWNE

ADDRESS P.O. Box 723 Hays, KS

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-04 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation LKC & Arb Depth to Top _____ Bottom T.D. 3635

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Arb. Lams - KC</u>	<u>oil</u>		<u>3635</u>			
<u>Arb</u>			<u>252</u>	<u>8 1/2 x 2 1/2</u>	<u>252</u>	<u>0</u>
<u>Arb</u>			<u>3634</u>	<u>5.500</u>	<u>3634</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Run tbg to 3500' Mix 100 SX 60/40 w/10% gel. w/400# hulls. Pull up to 1500' Mix 100 SX pull up to 600' circ cement to surface w/50 SX & 150# hulls. Pull rest of tbg. Hook up to 5 1/2" Mix 15 SX Press. to 200# & held. Hook up to 8 1/2" Mix 25 SX Press to 250# Done @ 2PM Jay Meifer KCC witness.

Name of Plugging Contractor Company Tools Stewart Well Ser. Berexco License No. 99998

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Curt Gabel

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]


(Address) P.O. Box 723, Hays, KS

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 2004

Marion Sue Vance
Notary Public

My Commission Expires: 4-30-06

MAR 02 2004
HAYS, KS



MAR 23 2004
Form 9-1
Revised 05-88
HAYS, KS

RECEIVED
MAR 26 2004
KCC WICHITA