

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room **RECEIVED**
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-30637-00,01

LEASE NAME Sunley ~~old~~ WO

WELL NUMBER #2

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 28 TWP. 14 RGE. 19 (E) or (W)

COUNTY Ellis

Date Well (Completed) _____

Plugging Commenced March 8, 2004

Plugging Completed March 8, 2004

MAR 25 2004 TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
KCC WICHITA office within 30 days.

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St. Suite 500 Denver, CO.

PHONE#(303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well SWD 26412

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 8, 2004 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top _____ Bottom _____ T.D. 3925'

Show depth and thickness of all water, oil and gas formations. 3837

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	0.	<u>206</u>	8 5/8"	<u>206</u>	none.
	Production Casing	0	<u>3808</u>	4 1/2"	<u>3808</u>	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Ran 2 3/8" tubing to 2103', circulated 110 sks of 60/40 POS with 10% Gel cement with 300 pounds of hulls to surface, pulled tubing and pumped 155 sacks of cement with 150#'s of hulls down 4 1/2" casing at 400#'s pressure ISIP 150#'s. Pumped 10 sks of cement with 50#'s of hulls down the 8 5/8" casing @ 400#'s. Cement in the 4 1/2 casing is from surface to 3875'. Plug down at 12:30 pm 3/8/04

Name of Plugging Contractor Fischer Well Service License No. 32332

Address Ellis, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company

STATE OF Colorado COUNTY OF Denver, 315.

Roland Nyp (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS

SUBSCRIBED AND SWORN TO before me this 18th day of March, 2004

Irene R Nyp
Notary Public

My Commission Expires: 9-30-04

