

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-1-1962
MAY 1 1962
CONSERVATION DIVISION
Wichita, Kansas

15-039-00425 00-00

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Decatur

Location: GSE NW Sec. 11 Twp. 1 Rge. _____ (E) _____ (W) 26

Name of Field: _____ Total Depth: 3630

I have this date completed supervision of plugging of:

Lease Name: Knutson Well No. 1

Operator's Full Name: Imperial Oil of Kansas

Complete Address: 780 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor: Southwest casing Pulling

Address: Great Bend, Kansas License No. W 399

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 2:30PM Day 27 Month 4 Year 62

The above well was plugged as follows:

7" 250' circulated with cement - 4 1/2" 3630' with 75 sax cement - PB to 3376'
perf 3331' - sand to 3320', set 3 sax cement with dump bailer.

Pulled 1610' 4 1/2" to 550', circulated hole with heavy mud through 4 1/2" at
550' (14 sax Gel), displaced 15 sax cement through 4 1/2" at 550', heavy mud
to 200', displaced 15 sax cement through 4 1/2" at 200', heavy mud to 40', set
plug and filled to 0' with cement.

Mudding and cementing by Halliburton Co.

Signed: Edson Peay
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 5/9/62
INV. NO. 4889-W