

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20195-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 1974
8-2-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name TGT Petroleum Corporation

Complete Address 209 East William St. Wichita, Kansas 67202

Lease Name Huff "A" Well No. 2

Location C NW NW Sec. 16 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3412'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3:30 P Day 31 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3412' 8 5/8 csg set at 272' cwe 200 sk.

5 1/2 csg set at 3410' cw 100 sk.

5 1/2 csg PBTB 3379' with top perf. (3183')

Set 5 1/2 wood plug at 3100' -poured 10' sand -dumped 4 sk cmt W/dump bailer. (3100-3060)

Cutoff and recovered 1399' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/100 lbs hulls -60 sk cem. -15 sk

gel & water & 50 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 8/2/74

INV. NO. 9652-W