

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

12-8-1970
RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

15-039-20200-00-00

Operator's Full Name Rosen Oil Corporation,
Complete Address 200 Sutton Place, Wichita, Kansas.
Lease Name Huff Well No. E-1
Location CNE-SE Sec. 17 Twp. 1 Rge. (E) (W) 26
County Decatur Total Depth 3403'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Sage Drilling Company, Incorporated,
Address 500 Bitting Building, Wichita, Ks. License No. _____
Operation Completed: Hour 5:00 PM Day 5 Month 12 Year 1970

The above well was plugged as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru
DP from 1075' to 750'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

12/8/70

INV. NO.

3021-W

Signed:

W. L. Nichols
Well Plugging Supervisor