

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20689-00-00
Spot: NWNESE Sec/Twnshp/Rge: 14-1S-26W
2310 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: COZAD E Well Number: 1
County: DECATUR Total Vertical Depth: 3517 feet

Operator License No.: 8981
Operator Name: ADECO, INC. & CHAMBERS
Address: BOX 873
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 209
Production: Size 4.5 feet: 3510 *114.30*
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/3/00
Plug Co. License No.: 8981 Plug Co. Name: ADECO, INC. & CHAMBERS
Proposal Rcvd. from: DEAN IVES Company: ADECO, INC. & CHAMBERS Phone: (785) 625-6010

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2000 12:30 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 209' w/250 sxs cwc. 4 1/2" set at 3510' w/250 sxs.
PBT 3487'. Prod. Perfs 3170' - 3482'. Squeezed 4 1/2" w/300 sxs w/500# hulls mixed in to Max. P.S.I. 500#. Held.
Squeezed 8 5/8" w/100 sxs cement blend to Max. P.S.I. 150#. Held. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 2000
10-16-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENT COMPANY.

Plugged through:

District: 04

Signed Carl Goodrow

KCC

INVOICED

(TECHNICIAN)

DATE 10/17/00

OCT 10 2000

Form CP-2/3

INV. NO. 2001060838

HAYS, KS

OCT 06 2000

LESTER L. CHAMBERS
 310 E. ASH
 OBERLIN, KS 67749
 CONTR ABERCROMBIE DRILLING CITY DECATUR FIELD LAWSON SE

REPLACEMENT CARD
 #1 "E" COZAD
 14-1-26W
 NW NE SE

| | | | |
|---|---|---|---|
| - | + | + | + |
| - | + | + | + |
| - | + | + | + |
| - | + | + | + |

GEOL MARK YOUNG CARD ISSUED 8/11/83 IP OIL WELL
 ELV 2360 KB SPD 7/2/83 LKC 3208-3322 OA
 2355 GL

| SMP | Tops | Depth/Datum |
|--------|-------------|-------------|
| ANH | 1831 + 529 | |
| TOR | 3165 - 805 | |
| LANS | 3172 - 812 | |
| ARB | 3490 - 1130 | |
| REAG | 3491 - 1131 | |
| GR WSH | 3492 - 1132 | |
| RTD | 3510 - 1150 | |

API 15-039-20,689
 8 5/8 " 210, 4 1/2 " 3510
 DST (1) 3143-3190 (TOR) / 15-30-30-60, REC 205' OIL SPKD
 DM, SIP 624-624#, FP 33-100, HP 1571-1562#, BHT 90'
 DST (2) 3192-3210 (LANS) / 15-30-30-60, 120' GIP, REC 20' CL
 GSY OIL, 35' HOCM, 15' OCM, SIP 450-442#, FP 42-58#, HP
 1612-1604#, BHT 91'
 DST (3) 3206-3230 (LANS) / 15-30-30-60, REC 5' HOCM, 10
 SOCM, SIP 558-558#, FP 25-33#, HP 1562-1554#
 MICT - CO, PF (LKC) 3320-22, W/ 4 SPF, AC 250G (15% MA) &
 100G (DEMUL), SWB DWN SO, PF (LKC) 3208-14, W/ 4 SPF, AC
 250G (15% MA), & 1000G (DEMUL), SWB DWN, SO, POP 8/4/83

INFO RELEASED: 11/15/84 - WAS OIL WELL - TIGHT HOLE
 NOTE: 8/11/83 ORIGINALLY FIRST REPORTED A.L. ABERCROMBIE
 AS OPERATOR

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS