

6010199

API NUMBER 15-039-20744-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 24, T. 1 S, R. 26 W/4

1650 feet from N/4 section line

330 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8981

Lease Name chambers Well # B-3

Operator: Adeco Inc chambers

County Decatur

Name & Address 310 E Ash

Well Total Depth 3635 127.23 feet

Oberlin Ks. 67749

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drlg. License Number 5422

Address 801 Union Center Wichita, Ks.

Company to plug at: Hour: AM Day: 3 Month: 9 Year: 19 84

Plugging proposal received from Walley Towns

(company name) Abercrombie Drlg. Co. (phone) _____

were: order 220 sx. cement 50/50 permix 670 gal. 3% C.C.

1 sx. hulls 1. 8 5/8 plug 1 sx. flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2444 Anhydrite 1921-51 Arbuck 6.3574-97

Dakota 1600 Plugging Proposal Received by Dale & Batthazor

844 = 1140

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None (circled)

Operations Completed: Hour: 9:30 AM Day: 3 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3520 for 30 mi.

25 SX @ 3520

25 SX @ 1930

100 SX @ 1140 mixed with 1 SX flow seal.

40 SX @ 260 dumped 1 SX hulls pushed plug to 40'

10 SX @ 40

Remarks: 10 SX Rat hole 10 SX mouse hole - Halliburton

(If additional description is necessary, use BACK of this form.)

I (and (circled)) conserve this plugging.

DATE 9-17-84

SEP 10 1984

Signed Dale & Batthazor SH

NOV 21 1984
CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)

INV. NO. 3116 OCT 12 1984

SH
sp7
26