

4-032357

15-039-20265-00-01

S-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,265-A

NW NE /4 SEC. 22, 01, 26 W
660 feet from N section line
1980 feet from E section line

Operator license# 5393

Lease: Mapes Well # 22-2

Operator: A.L. Abercrombie, Inc.

County: Decatur 108.88

Address: Rt. 1 - Box 56
Great Bend, Kansas 67530

Well total depth 3350 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: A.L. Abercrombie, Inc. License# 5393

Address: Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 19 Month: May Year: 1999

Plugging proposal received from: Bill Sowals

Company: A.L. Abercrombie, Inc. Phone: -

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:30 A.M., Day: 19 Month: May Year: 1999

Actual plugging report: 8 5/8" set at 219' w/170 sxs cwc. 4 1/2" set at 3345' w/150 sxs.
Perfs at 3268' - 3270'. Squeezed 4 1/2" w/165 sxs cement blend with 500# hulls mixed in to
Max. P.S.I. 300#. S.I.P. 200#.
Squeezed 8 5/8" w/12 sxs to Max. P.S.I. 300#. S.I.P. 300#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

STATE CORPORATION COMMISSION

RECEIVED JUN 04 1999 6-4-1999 CONSERVATION DIVISION Wichita, Kansas

Form CP-2/3

KCC

JUN 01 1999

HAYS, KS

INVOICED


DATE 6-9-99

INV. NO. 61009

S-19

OXFORD EXPLORATION COMPANY #22-2 RICHARDS 22-1-26W
 1550 DENVER CLUB BLDG. C NW NE
 DENVER, CO. 80202
 CONTR MURFIN DRILLING CO. CTY DECATUR

GEOL _____ FIELD MAPES
 E 2444 KB CM E 8/10/81 CARD ISSUED 12/23/81 IP TIGHT HOLE



API 15-039-20,265-A

LOG	TOPS	DEPTH	DATUM
*ANH		1902	+ 542
*B ANH		1931	+ 513
HEEB		3198	- 754
TOR		3233	- 789
LKC		3240	- 796
B KC		3447	-1003
GR W		3558	-1114
RTD		3580	-1136
LTD		3581	-1137
*SMP TOPS			

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

OLD INFO: OPERATOR WAS ABERCROMBIE
 DRLG., INC., #2 RICHARDS, SPD 4/30/73,
 SET 8-5/8" 219/170SX, COMPLETED AS
 D&A/GR W 5/8/73
 DST (1) 3234-3243/15-45-60-45, REC 298'
 MW W/OIL SPKS, SIP 857-826#, FP 21-
 53/95-234#
 DST (2) 3254-3273/30-45-60-45, REC 60'
 OIL, 120' OCM, 160' MW, SIP 867-
 857#, FP 42-42/85-170#
 DST (3) 3269-3285/15-45-30-45, REC 30'
 M W/F OIL SPKS, SIP 983-899#, FP
 21-21/31-21#
 DST (4) 3397-3420/15-45-60-45, REC
 1230' WTR, SIP 627-637#, FP 512-
 (OVER)

OXFORD EXPLORATION COMPANY #22-2 RICHARDS 22-1-26W
 C NW NE

502/575-606#
 DST (5) 3269-3280 W/SP(30'ZN)/30-45-30-45, REC 12' FL (12' OCM,
 10% OIL & 2' FO), SIP 489-129#, FP 14-14/19-19#

NEW INFO: RE-ENTERED EST 8/10/81
 WSH DWN - SET PROD CSG - MICT - CO,
 TSTD, (FORM & INTV NA), POP - TIGHT
 HOLE - NO OTHER INFO TO BE RELEASED
 AT PRESENT - WILL RELEASE INFO WHEN
 AVAILABLE