

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20501-00-00  
Spot: SESW Sec/Twnshp/Rge: 31-30S-32W  
660 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: MILLER TRUST Well #: 1-31  
County: HASKELL Total Vertical Depth: 5790 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

CIBP Size: feet: 4830 WITH 2 SX CMT  
PROD Size: 4.5 feet: 5118 WITH 475 SX CMT  
SURF Size: 8.625 feet: 1853 WITH 700 SX CMT

31 188' 18

Well Type: OIL UIC Docket No: - Date/Time to Plug: 03/24/2004 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: CIBP @ 4830'. PLUG AT 1880' WITH 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT. 20 SX GEL FOR SPACER.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/24/2004 11:10 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5064'. CIBP @ 4830' WITH 2 SX CMT. 1ST PLUG PULL TO 1880' & SPOT 20 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 650' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4994	4996		
4954	4958		
4889	4893		
4881	4885		

RECEIVED  
MAR 29 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2027' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
MAR 25 2004  
KCC Dodge City

Signed

(TECHNICIAN)

INVOICED

DATE 3-29-04  
VV, NO. 2004061344

Form 54-2/3