

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20375-00-01
Spot: S2S2SW Sec/Twnshp/Rge: 31-14S-27W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: COBERLY Well #: 1
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

PROD Size: 5.5 feet: 4272 190 SX CMT
SURF Size: 8.625 feet: 289 175 SX CMT

\$141,38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JERRY GREEN Company: CASTLE RESOURCES, INC. Phone: (785) 625-5155

Proposed Plugging Method: Ordered 275 sxs cement - 14 sxs gel - 800# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2004 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 289' w/175 sxs cement.
5 1/2" casing at 4272' w/190 sxs cement.
Port collar at 1989' w/300 sxs cement.
Tied to 5 1/2" casing - spotted 50 sxs cement with 300# hulls - 14 sxs gel with 200# hulls.
225 sxs cement with 300# hulls at 250# pressure.
Shut well in.
03/15/2004 - Ran wireline - topped off with additional 6 sxs cement.
Visual inspection of annulus revealed cement in casing head.

Perfs:

Top	Bot	Thru	Comments
4210	4230		
3966	3970		

RECEIVED
MAR 26 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

PO

Signed

Roger Moses

(TECHNICIAN)

INVOICED

DATE 3.26.04

INV. NO. 2004061327

Form CP-2/3

MAR 23 2004

CASTLE RESOURCES
HAYS, KS 67601

31-14-27W
C S/2 S/2 SW

#1 COBERLY OWWO

site: 11-3/4 S & 6-1/4 E OF GOVE, KS city: GOVE API 15-063-20375-A
 contr: EMPHASIS OIL OPERATIONS field: LEIGHTON
 geol: JERRY GREEN

if date 07/25/89 spd date 07/27/89 drlg comp 07/30/89 card issued 08/30/89 last revised 08/30/89

ELV: 2533 KB LOG	
tops.....	depth/datum
ANH.....	1961 +572
VB/ANH.....	2000 +533
HEEB.....	3674 -1141
TOR.....	3696 -1163
LANS.....	3710 -1177
STARK.....	3956 -1423
FT SC.....	4206 -1673
CHER LWR.....	4234 -1701
RTD OLD.....	4250 -1717
LTD OLD.....	4251 -1718
MISS-NOT REACHED	
DOTD.....	4350 -1817

IP status:
 OIL, P 120 BOPD, NW, MARM 4211-4228 OA, (NEW PAY)
 ,
 OLD INFO: OPERATOR WAS DONALD C. SLAWSON, 1
 COBERLY "GGG", SPD 06/01/78 , 06/09/78 SET 8-5/8"
 289/175SX, D&A, CHER , 06/09/78 (CARD ISSUED
 06/29/78)
 CONTR: SLAWSON DRILLING COMPANY, INC.
 GEOL: DON MOORE
 NO. CORES
 DST (1) 3860-3922 (LANS H,I), / 30-45-45-30, REC 315'
 SLI GCMSW, W / SCUM OIL ISIP 1064# FSIP 1064#
 IFP 50# -110# FFP 121# -191#

COPYRIGHT 1989
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)

CASTLE RESOURCES
HAYS, KS 67601

31-14 -27W
C S/2 S/2 SW

#1 COBERLY OWWO

DST (2) 3944-3963 (LANS J), / 30-60-45-60, REC 10' OIL (GR 36), 62' OCM ISIP 100# FSIP 80# IFP 30# -40# FFP 50# -50#
 DST (3) 3954-3982 (LANS K), / 30-45-45-60, 992' GIP, REC 62' CLEAN GSY OIL (GR 37), 310' HMCO (63% O & 37% M) ISIP 1124# FSIP 1104# IFP 30# -80# FFP 110# -141# BHT 128 °
 DST (4) 3952-3980 (LANS K), / 30-60-60-90, 1010' GIP, REC 176' HVLY OILY CGM (50% M, 40% OIL, 10% W), 63' OILY CGM, 63' SLI OCGM (18% OIL) ISIP 1133# FSIP 1123# IFP 40# -81# FFP 91# -122#

NEW INFO: FR 07/25/89 , RE-ENTERED 07/27/89 WSH DWN TO 4251, DD-4350 TD DC 07/30/89
 CSG: SET 5-1/2" 4272 / 190 SX MICT - CO, PF (FT SC) 1/4228, 1/4211, AC 750 GAL (MA), ON VAC, UNABLE TO SWB BELOW 2000', SWB 80 BOPH, NW, POP (8/18/89), P 120 BOPD, NW (GR 41.8), REG PMP STRK AT 9 SPM, 54 STROKE - NEW PAY (LANS K PAY REMAINS BEHIND PIPE)