

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20785-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 21-16S-10W  
4950 feet from S Section Line, 1930 feet from W Section Line  
Lease Name: KOZISEK TWIN Well #: 2-A  
County: ELLSWORTH Total Vertical Depth: 3400 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3400  
SURF Size: 8.625 feet: 250

\$110<sup>00</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2004 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: BRIAN SCHUMOCHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Sand perms to 2860' and put 5 sxs cement on top. Cut off 5-1/2" casing; pull to 1375'; and pump 35 sxs. Pull casing to 1050' and pump 35 sxs. Pull casing to 640' and pump 35 sxs. Pull casing to 300' and circulate to surface.  
Plugging Method:

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

RECEIVED  
KCC DISTRICT #2

Date/Time Plugging Completed: 03/12/2004 2:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MAR 25 2004

Sanded perforations to 2860' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1800' and pulled to 1375'. Pumped 35 sacks of cement with 150 lbs cotton hulls and pulled casing to 1050'. Pumped 35 sacks of cement with 150 lbs cotton hulls and pulled casing to 640'. Pumped 35 sacks of cement with 100 lbs cotton hulls and pulled casing to 300'. Circulated to surface with 100 lbs cotton hulls.

WICHITA, KS

60/40 posmix with 4% gel.

Remarks: COPELAND CEMENT #24226

Plugged through: CSG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

INVOICED

DATE

3-29-04

TIME

2004061349