

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20078-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 3-17S-10W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: BREDFORD C Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3277 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3273  
SURF Size: 8.625 feet: 264

\$ 106<sup>50</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2004 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand open hole to 3225' and put 5 sxs cement on top. Cut off 5-1/2" and pull to 1300'. Pump 35 sxs and pull casing to 975'. Pump 35 sxs and pull casing to 575'. Pump 35 sxs and pull casing to 315'. Circulate cement to surface. 60/40 posmix with 4% gel.

RECEIVED  
KCC DISTRICT #2

Plugging Proposal Received By: VIRGIL CLOTHIER  
Date/Time Plugging Completed: 03/10/2004 11:00 AM

WitnessType: PARTIAL  
KCC Agent: VIRGIL CLOTHIER

MAR 29 2004

Actual Plugging Report:

Perfs:

WICHITA, KS

Sanded open hole to 3200' and put 5 sacks of cement on top. Perforated at 1300', 975', 575', and 315'. Ran tubing to 1300' and pumped 35 sacks of cement with 150 lbs of cotton hulls. Pulled tubing to 975' and pumped 35 sacks of cement with 150 lbs of cotton hulls. Pulled tubing to 575' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 315' and circulated cement to surface with 100 lbs cotton hulls.

60/40 posmix with 4% gel.

Remarks: COPELAND CEMENT #24222

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 3-29-04  
VV. NO. 2004061349