

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01371-00-00  
Spot: NWNE Sec/Twnshp/Rge: 3-25S-3E  
5081 feet from S Section Line, 1105 feet from E Section Line  
Lease Name: BRAINERD Well #: 1  
County: BUTLER Total Vertical Depth: 2745 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: ONE NORTH HUDSON, SIXTH FLOOR  
OKLAHOMA CITY, OK 73102

COND Size: 0 feet: 0  
PROD Size: 5.5 feet: 2738 25 SX CMT  
SURF Size: 8 feet: 2450

*Handwritten:* \$ 8921

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2004 12:00 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING  
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY COMPANY Phone: (316) 321-0550

Proposed Plugging Method:

See actual report.

RECEIVED  
KCC DISTRICT #2  
MAR 24 2004

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2004 12:00 PM KCC Agent: DONALD HOBERECHT

**Actual Plugging Report:**

2/27/2004 Well has been plugged back to 2700'. No casing recovery. Perforated casing at 250'. Ran 1" tubing to 250'. Pumped 165 sacks of cement. Did not circulate.

3/11/2004 Found top cement at 105'. Ran 1" tubing to 100'. Pumped 250 sacks of cement and filled to 20'.

3/12/2004 Dumped 5 yards of slurry mix. Filled from 20' to surface.

60/40 posmix with 4% gel.

Braden Cementing and Lewis & West Redi Mix.

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 26 2004  
CONSERVATION DIVISION  
WICHITA, KS

**Perfs:**

Top	Bot	Thru	Comments
2738	2745		

Remarks:

Plugged through: TBG

District: 02

Signed: *[Signature]*

(TECHNICIAN)

**INVOICED**  
DATE 3-26-04  
INV. NO. 2004061331