

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21462-00-00
Spot: SWNESW Sec/Twnshp/Rge: 21-9S-21W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DARNELL Well #: 1
County: GRAHAM Total Vertical Depth: 4003 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

CIBP Size: feet: 3813
CIBP Size: feet: 3845
PROD Size: 4.5 feet: 3984 285 SX CMT
SURF Size: 8.625 feet: 247 225 SX CMT

\$130¹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 628-3449

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls.
CIBP at 3813'. Production perms - Arbuckle 3798' - 3800'.
No squeeze records. Perforate anhy at 1775'. Base Dakota at 1025'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2004 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

E.L.I. Perforated Anhy. at 1775' and Base Dakota at 1025'.
Allied took injection rate 4 BPM at 500#. Backside dead.
Allied pumped 200 sxs cement with 600# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to backside. Instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3938	3942		
3893	3896		
3874	3880		
3864	3868		
3852	3856		
3827	3833		
3808	3810		
3800	3806		
3798	3800		

RECEIVED
MAR 26 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 3-26-04
INV. NO. 2004061333

Form CP-2/3

MAR 25 2004

EXCEL ENERGY CORP
 1800 GLENARM PLACE #1100
 DENVER, CO 80202
 CONTR C&R DRILLING CO

21-9-21W
 SW NE SW

#1 DARNELL

CTY GRAHAM

GEOL

FIELD MOREL

S 2277 KB. CW 7/13/81 CARD ISSUED 11/25/81 P 13 BO & 90 BMDP
 API 15-065-21,462 ARB 3800-3806

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
SC	1736	-	± 541
TOP	3234	-	957
OREAD	3389	-	1112
HEEB	3445	-	1168
TOR	3451	-	1174
LANS	3472	-	1195
BKC	3700	-	1423
AIT	3731	-	1454
ET SC	3765	-	1488
PRE GAMB	3788	-	1511
ARB	3796	-	1519
RTD	4003	-	1726

8 5/8" 247/225SX; 4 1/2" 3984/285SX

DST (1) 3795-3833(ARB)/30-60-60-92;
 650' FL (45% OIL, 5% G, 43% W), 1370'
 FL (15% G, 35% OIL, 50% W), 130' FL (3%
 G, 5% OIL, 90% WTR); SIP 966-966#
 FP 243-866/866-966#; HP 2187-206
 MICT -- CO, PF (ARB) 8/3938-42, 6/3893-
 96, 12/3874-80, 8/3864-68, 8/3852-56
 AC600G, SWB DWN W/SSO, SET BP, PF (ARB)
 12/3800-06, AC250G, SWB DWN W/GSO, POS
 P 13 BO & 90 BMDP 11/17/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS