

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20797-00-00
Spot: CN2SWSW Sec/Twnshp/Rge: 18-1S-26W
990 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: POWELL Well Number: 1-18
County: DECATUR Total Vertical Depth: 3520 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: PO BOX 450 408 MAIN
ATWOOD, KS 67730

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 257
Production: Size 4.5 feet: 3515
Liner: Size feet:

\$114.40

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/25/2001 12:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 9 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 05/25/2001 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 257' w/175 sxs cwc. 4 1/2" set at 3515' w/175 sxs.
Port collar 1916' w/400 sxs cwc.
Fluid level at 3000'.
Filled hole with 9 yards Redi-Mix.
Prod. Perfs 3352' - 3373'.
Plug complete.

INVOICED

DATE 6-6-01
TEL. NO. 2001061887

RECEIVED
KANSAS CORPORATION COMMISSION
6-6-2001
JUN 6 2001

CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

110

MAY 30 2001

MURFIN DRILLING COMPANY
WICHITA, KS 67202

#1-18 POWER

18-01 -26W
C N/2 SW SW

replacement card

site: 8-1/4 N & 5 W OF NORCATUR, KS
contr: COMPANY TOOLS

city: DECATUR
field: WC (BLEES SW DISC)

AP 15-039-20797

geol: RICH BELL
date 10/02/86

spd date 10/08/86
dthg date 10/14/86
comp

ELV: 2425 KB LOG
tops.....depth/datum
HEEB.....3158 -733
TOR.....3196 -771
LANS.....3200 -775
BKG.....3406 -981
PBTD.....3472 -1047
RTD.....3520 -1095

IP status:
OIL, P 16 BOPD, NW, LKC 3352-3373 OA,
CSG: 8-5/8" 257 / 175 SX, 4-1/2" 3515 / 175 SX, MULTI
STAGE COLLAR AT 1916 / 400 SX
NO CORES
DST (1) 3158-3215 TOR, LANS A, / 45-45-45-45, REC
60" OIL SPTD M, 60" M. ISIP 1062# FSIP 1051# IFP
65# -65# FFP 76# -76# IHP 1673# FHP 1662#

INFO RELEASED: 2/3/88 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)