

To: 6 031288
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-5
API NUMBER 15-039-00209-00-00

C SW NW, SEC. 16, T 1 S, R 26 W/E

3300 feet from S section line

4620 feet from E section line

Lease Name Huff Well # 1

County Decatur 114.63

Well Total Depth 3527 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 203

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Operator: Mustang Companies Inc.
Name & Address: Box 1609
Great Bend, Ks. 67503

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 5 Month: Oct Year: 19 89

Plugging proposal received from Clark

(company name) Mustang Co. Inc. (phone)

were: 8 5/8" set at 208' w/175 sks. 4 1/2" set at 3309' w/135 sks. Perf 3236'. Holes in casing 1250' and 1800'. PBTD 3270'. Order 350 sks 65/35 poz 10% gel. Allied Cement Co. 500#. LaRue Water. Poe Well Service rig.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 PM Day: 5 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1866' circulated cement blend.

Hook onto 4 1/2" and squeezed to max psi 700#. Close in psi 400# w/ total of 250 sks. Cement blend w/400 # Hulls. Hook onto 8 5/8" annulus. Squeeze w/100 sks and 100# hulls. o Max psi 400#. Close in psi 200#. Plug complete.

Remarks: 10-20-89

(If additional description is necessary, use BACK of this form.)

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE 10-25-89

INV. NO. 26225

Carl Goodrow