

9-915-039-20100-00-00

6 031159

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1969

C SE SW, SEC. 16, T 1 S, R 26 W 1/4

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Huff Well # B 1

Operator: T.G.T. Pet Corp

County Decatur 113.75

Name & Address 209 E. William

Well Total Depth 3500 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well  Gas  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 9 Month: Sept Year: 19 88

Plugging proposal received from Eldon Folmsbee

(company name) T.G.T. (phone)

were: 8 5/8" set at 247' w/175 sks cwc. 4 1/2" set at 3499' w/125 sks.

Perf 3170' - 3348'. Order sand and Common Cement. Recover pipe. Order 250 sks

60/40 Poz 8% Gel 3% Ca Cl 500# Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30PM Day: 9 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3100' w/4 sks Common Cement on sand w/bailer

2 shots recovered 1010' of 4 1/2" casing, First at 1200'. Squeeze 8 5/8" w/250 sks cement w/500# Hulls mixed in to max psi 500#. Close in psi 500#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-26-88

INV. NO. 22736

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow