

9-8 15-039-20153-00-00

6 031160

API NUMBER 15- 1970

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SW, SEC. 16, T 1 S, R 26 W/E

660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Operator: TGT Petroleum Corp

Name & Address: 209 East Williams

Wichita, Ks. 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988
10-21-1988
CONSERVATION DIVISION
Wichita, Kansas

Lease Name Huff Well # B-2

County Decatur 110.99

Well Total Depth 3415 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 9 Month: Sept Year: 19 88

Plugging proposal received from Eldon Folmsbee

(company name) T.G.T. (phone)

were: 8 5/8" set at 257' w/225 sks cwc. 4 1/2" set at 3414' w/125 sks.

Perf 3192' - 3280'. Order sand and Common Cement. Pd11 pipe. Order 250 sks 60/40

Poz 8% Gel 3% Ca Cl 500# Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30AM Day: 9 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3140' w/4 sks Common Cement on sand w/bailer.

One shot recovered 1200' of 4 1/2" casing. Squeezed 8 5/8" w/250 sks cement w/500# Hulls mixed in to max psi 300#. Close in psi 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-26-88

INV. NO. 22735

Signed Carl Goodrow (TECHNICIAN)