

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20332-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 2-33S-15W  
4345 feet from S Section Line, 2506 feet from E Section Line  
Lease Name: DEGEER TWIN Well #: 2  
County: BARBER Total Vertical Depth: 4337 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 155 N. MARKET - SUITE 900  
WICHITA, KS 67202

CIBP Size: feet: 2300 WITH 2 SX CMT  
PROD Size: 5.5 feet: 2722 WITH 150 SX CMT  
SURF Size: 10.75 feet: 248

*\$14095*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2004 10:30 AM

Plug Co. License No.: 32302 Plug Co. Name: KEY GAS CORP.

Proposal Rcvd. from: MIKE MCNAUL Company: \_\_\_\_\_ Phone: (316) 265-2270

Proposed Plugging Method: CIBP @ 2300' & 2 SX CMT OR PUMP 200# HULLS & 25 SX CMT DISPLACED TO 2200'. PERFORATE AT 900' & CIRCULATE CMT TO SURFACE UP 10 3/4" 7 5 1/2" ANNULUS. MINIMUM OF 400 SX CMT ON LOCATION OR PULL PIPE. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/19/2004 1:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 2600'. SET CIBP @ 2300' WITH 2 SX CMT ON TOP. SPOT 15 SX GEL & 230 SX CMT AT 587'. CIRCULATE CMT TO SURFACE. PULLED 1 JOINT OF 5 1/2", PIPE STUCK. CIRCULATE CMT TO SURFACE AT 587'.

Perfs:

Top	Bot	Thru	Comments
2390	2395		
2310	2315		

RECEIVED


MAR 25 2004

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY GRESSEL OILFIELD SERVICES. RECOVERED 30' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE

3-26-04

INV. NO.

2004061337

Form