

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20523-00-00  
Spot: NESW Sec/Twnshp/Rge: 14-33S-30W  
1980 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: HAMM Well #: 3  
County: MEADE Total Vertical Depth: 5450 feet

Operator License No.: 32126  
Op Name: ROBERTS, GERALD M DBA SUNFIRE E  
Address: BOX 1761 701 S. PARKWAY BLVD.  
LIBERAL, KS 67901

CIBP Size: feet: 5410  
COND Size: 20 feet: 43 4.50 YRDS. 65 SX GROUT  
PROD Size: 4.5 feet: 5450 WITH 350 SX CMT  
SURF Size: 8.625 feet: 1623 WITH 800 SX CMT

8177'13

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2004 11:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2004 10:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5410'. PUMP 200# HULLS & 20 SX CMT. DISPLACE TO BOTTOM WITH 76 BBL MUD. PRESSURED TO 500 PSIG & SHUT IN. 03/15/04: 1ST PLUG PULL OUT OF HOLE TO 1650'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE TO BOTTOM WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. SDON. 3/16/04: LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5207	5210		

RECEIVED  
MAR 25 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2503' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Jim Holland* PART II  
(TECHNICIAN)

INVOICED

DATE 3-26-04

CALL NO. 2004061342

Form 09/2/3