

KANSAS

*10*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1973 5-9-73  
CONSERVATION DIVISION  
Wichita, Kansas

*15-039-20265-00-00*

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Richards Well No. 2

Location NW-NE Sec. 22 Twp. 1 Rge. (E) (W)26

County Decatur Total Depth 3580'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:15 AM Day 8 Month 5 Year 1973

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 170 Sx. (6 3/4" Hole).  
Top of Dakota section @ 935'.

Circulated hole with heavy mud. Pulled DP to 1160' and displaced 70 Cu. Ft. cement  
thru DP from 1160' to 835'. Pulled DP to 245' and displaced 25 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/11/73  
INV. NO. 7345-W

Signed: *H. L. Nichols*  
Well Plugging Supervisor