

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAR 25 2004
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kera-Oil
Address: 3406 E. 28th Avenue, Hutchinson, Kansas 67502
Phone: (620) 664-6658 Operator License #: 32005
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: February 15, 2004 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 3326' Bottom: 3579' T.D. 3670'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185 - 0198100 - 00
Lease Name: Fisher "B"
Well Number: #2
Spot Location (QQQQ): SE - SE - NW -
2970' Feet from North / South Section Line
2970' Feet from East / West Section Line
Sec. 17 Twp. 21 S. R. 13 East West
County: Stafford
Date Well Completed: November 15, 1951
Plugging Commenced: February 16, 2004
Plugging Completed: February 17, 2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	365'	8-5/8"	365'	0'
	Production	0'	3663'	5-1/2"	3663'	2104.48'
	<u>CBP</u>		<u>3579</u>			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Run bailer to bottom. Fluid is at 2700' from surface. Garb's Welding cut ring off casing head. Paul's Oilfield helped sand off to 3275'. Got 80 barrels down hole. Waited 1 hour and spot 5 sxs cement. Rigged up jacks, pulled stretch and worked a bit. Next day, lay down bailer and rigged up knife. Cut casing @ approximately 2150'. Jack casing out a bit and pulled to 800'. Rigged up Copeland. Pumped 10 sxs gel and 50 sxs cement-pull to 390'-pumped 50 sxs cement-pull to 40'-pumped 20 sxs. Pulled 65 jts. total. R.D.M.O.


Name of Plugging Contractor: D.S.&W. Well Servicing, Inc License #: 6901

Address: P.O. Box 231, Claflin, Ks 67525

Name of Party Responsible for Plugging Fees: Kera-Oil

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 **KAREN J. MITCHELL**
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Ks. 67525

SUBSCRIBED and SWORN TO before me this 24th day of March, 20 04

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202