

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
120 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117

RECEIVED

API NUMBER 15-135-214263-0000 <sup>24263-00-00</sup>  
LEASE NAME Pavlu 'A'  
WELL NUMBER 1-2

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

MAR 25 2004

KCC WICHITA

1249 Ft. from South Line of Section  
731 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION 100' SE of C W/2 SW  
ADDRESS 8080 E. Central Section 2 Township 19s Range 24w  
CITY, STATE, ZIP Wichita, Kansas 67206 County Ness  
PHONE # 316-636-2737 Date Well Completed 03/20/04 3/19/04  
Character of Well Dry and Abandoned Date Plugging Commenced 03/20/04 3/19/04  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 03/20/04 3/19/04

The plugging proposal was approved on March 18, 2004 (date)  
by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4352  
Show depth and thickness of all water, oil and gas formations. 4400

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds <u>1 surf</u>	Shale	200	<u>201</u> <del>215</del>	8-5/8"	<u>200</u> <u>211</u>	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Received plugging orders on 03/18/04 at 2:00 pm from Steve Pfeifer. Plugged in following manner beginning at 11:30 am on 03/19/04: Used 225 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug at 1605' - 50sx, 2nd plug at 750' - 80sx, 3rd plug at 375' - 30sx, 4th plug at 240'-40sx, top plug at 40'-10 sx, cemented to surface. Rathole - 15sx, no mousehole. Plug down at 2:00 pm on 03/19/04. Allied Cementing ticket #18256.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 24th day of March, 2004



*Pamela S. Fields*  
(Notary Public)

My Commission Expires: \_\_\_\_\_

RECEIVED  
 MAR 25 2004  
 KCC WICHITA

**Sterling Drilling Company, Rig #4**

Box 1006, Pratt, Kansas 67124-1006  
 Office Phone (620) 672-9508, Fax 672-9509

**SAMPLE LOG**

**Pavlu 'A' 1-2**

**LOCATION:** 100' SE of C W/2 SW Section 2 T 19s R 24w  
**API:** 15-135-214263-0000 Ness County, Kansas

**OWNER:** McCoy Petroleum Corporation  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 03/10/04  
**COMPLETED:** 03/19/04

**TOTAL DEPTH:** **DRILLER** 4352 FEET  
**LOGGER** 4358 FEET

**Ground Elevation:** 2304  
**KB Elevation:** 2313

**LOG**

0 -	4 FEET	Surface Soils
4 -	180 FEET	Sand and Clay
180 -	1565 FEET	Redbeds
1565 -	1605 FEET	Anhydrite (Driller's)
1605 -	2400 FEET	Shales and Salt
2400 -	4352 FEET	Limestone/Shales

**CASING RECORDS**

**Surface Casing:**

Spud @ 2:45 am on 03/10/04. Drilled 12-1/4" hole to 215'. Ran 5 joints of new 23# 8-5/8" surface casing tally 200.81' set at 211.81' KB, Cemented with 150 sx Common; 3% CC, 2% Gel. Plug down at 8:00 pm on 03/10/04. Cement did circulate. Swift Cementing ticket #6612. Welded straps on bottom 3 joints & welded collars on remainder.

**Plugging Data:**

Received plugging orders on 03/18/04 at 2:00 pm from Steve Pfeiffer. Plugged in following manner beginning at 11:30 am on 03/19/04: Used 225 sx of 60/40 Poz; 6% Gel; 1/4# Floseal. Heavy mud in hole; bottom plug at 1605' - 50sx, 2nd plug at 750' - 80sx, 3rd plug at 375' - 30sx, 4th plug at 240'-40sx, top plug at 40'-10 sx, cemented to surface. Rathole - 15sx, no mousehole. Plug down at 2:00 pm on 03/19/04. Allied Cementing ticket #18256.

**DEVIATION SURVEYS**

3/4 degree(s) at	215	feet
1-1/2 degree(s) at	3865	feet
3/4 degree(s) at	4275	feet