

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-039-00209-00-00

API NUMBER _____

LEASE NAME HUFF

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 16 TWP. 1S RGE. 26W ~~Kear~~ (W)

COUNTY Decatur

Date Well Completed 10-03-63

Plugging Commenced 10-05-89

Plugging Completed 10-05-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Companies, Inc.

ADDRESS P.O. Box 1609, Great Bend, KS 67530

PHONE# (316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 18, 1989 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top _____ Bottom T.D. 3527'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	208'	none
				4 1/2"	3309'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Run tubing to 1866', pump 100 sx 65/35 poz, 10% gel, 2 sx hulls-circulate cement, pull tubing.

Pump 150 sx with 2 sx hulls down 4 1/2" casing, max press 700#, ISDP 400#. Pump 100 sx with 1 sx hulls down 8 5/8" casing @ 400#, ISDP 200#. Release pressure on 4 1/2" casing, cement held @ 2' below top of casing. Release pressure on 8 5/8" casing, no pressure or vacuum.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____

Address P.O. Box 31, Russell, KS 67665

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MUSTANG COMPANIES, INC.

STATE OF Kansas COUNTY OF Barton, ss. NOV - 2 1989

NOV - 2 1989
CONSERVATION DIVISION
Wichita, Kansas

Raford Clark (Employee of Operation) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Raford Clark

(Address) P.O. Box 1609

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1989

Pamela K. Walters

My Commission Expires: August 25, 1991 Notary Public
Pamela K. Walters

15-039-00209-00-00

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

old

ALLIED CEMENTING CO., INC.

No. 5930

Home Office P. O. Box 31

Russell, Kansas 67665

Date	10-5-89	Sec.	16	Twp.	1 ^s	Range	26 ^w	Called Out	6:45 A.M.	On Location	10:00 A.M.	Job Start	10:45 A.M.	Finish	1:30 P.M.
Lease	Huff	Well No.	1	Location			Lyle 2W 1/2 N 1/4 E			County	Decatur	State	Ks.		

Contractor	Poc. Well Service	
Type Job	P = A	
Hole Size	7 7/8"	T.D. 3310'
Csg.	4 1/2"	Depth 3309'
Csg. Tbg. Size	8 7/8"	Depth 208'
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.		Minimum
Meas Line		Displace
Perf.		

Owner	Same
To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	Mustang Companies Inc.
Street	
City	State
The above was done to satisfaction and supervision of owner agent or contractor	
Purchase Order No.	
X	<i>[Signature]</i>

EQUIPMENT		
No.	Cementor	
Pumptrk 191	Helper	Gary H. Wayne Mc
No.	Cementor	
Pumptrk	Helper	
	Driver	Mark D.
Bulktrk #156	Driver	

CEMENT	
Amount Ordered	350 stks 65/35 poz 10 lb gel
Consisting of	4 5 stks hulls.
Common	
Poz. Mix	
Gel.	
Chloride	
Quickset	
Sales Tax	

DEPTH of Job		
Reference:	#10 Pumptruck - plug	\$340.00
	#14 mileage @ 1.00/mi.	251.00
	Sub Total	\$591.00
	Tax	
	Total	

Handling	\$90 4/stk.
Mileage	\$203 4/stk./mi. (25 mi.)
Sub Total	
Total	
Floating Equipment	

Remarks: Ran log to 1860'. Circulated cement to surface with 100 stks cement & 2 stks hulls. Pulled log. Tool into 4 1/2" csg. mixed 150 stks cement with 2 stks hulls at 700" max. pressure & shut in at 400". Down annulus (3 7/8" csg.) at 400" max. pressure, mixed 100 stks cement with 1 st. hulls, & shut in at 200'.

Thanks
 NOV - 2 1989
 11-2-1989
 CONSERVATION DIVISION
 Wichita, Kansas