

15-039-20100-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.--82-3-117

#4 ✓

API NUMBER \_\_\_\_\_

LEASE NAME Huff

WELL NUMBER B #1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 16 TWP. 1 RGE. 26W (E) or (W)

COUNTY Decatur

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/8/88

Plugging Completed 9/9/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR T G T Petroleum Corporation

ADDRESS 209 E. William #615  
Wichita, KS 67202

PHONE#(316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	247	none
				4 1/2	3499	1014

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3170', ran 4 sacks cement. Shot @1245', 1212', 1014'. Plugged surface with 250 sacks cement, 500# hulls 60/40 pos 8% gel 2%cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 88

[Signature]  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
9-16-1988  
SEP 16 1988  
REGISTRATION DIVISION  
Wichita, Kansas

Commission Expires: \_\_\_\_\_



KANSAS  
Wichita, Kan. 67202  
MAR 7 1970

16-1-26W  
CSE SW

WELL LOG

15-039-20100-  
00-00

Company: Donald C. Slawson  
Suite 408 One Twenty Building  
Wichita, Kansas 67202

Lease: Huff 'B' #1  
App. C SE SW, Section 16-1-26W  
Decatur County, Kansas

Total Depth: 3500' Elevation: 2398 K.B.

Contractor: Slawson Drilling Company, Inc.

Commenced: July 25, 1969

Completed: August 1, 1969

Casing: 8 5/8" at 247' with 175 sx cement  
4 1/2" at 3499' with 125 sx cement

10 BOPD

anhydrite 1853  
1880  
Bed "


0-247	Surface Clay
247-1630	Shale & Shells
1630-1854	Shale & Lime
1854-1881	Anhydrite
1881-2575	Shale & Lime
2575-2904	Lime & Shale
2904-3500	Lime
3500	Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1974  
4-23-74  
CONSERVATION DIVISION  
Wichita, Kansas


STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

Wichita Geological Society

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Huff 'B' #1 well.

  
DONALD C. SLAWSON

Subscribed and sworn to before me this 15th day of August, 1969.



  
Linda R. Sparr, Notary Public