

15-039-20338-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Decatur County, Sec. 16 Twp. 1S Rge. 26 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW SE

Lease Owner Baird Oil Company, Inc.

Lease Name ANTHONY Well No. 2

Office Address Logan, Kansas 67646

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed June 21 1976

Application for plugging filed (verbally) June 21 1976

Application for plugging approved (verbally) June 21 1976

Plugging commenced June 21 1976

Plugging completed June 21 1976

Reason for abandonment of well or producing formation
No commercial quantity of gas or oil encountered.


If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3465'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211 K.B.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

- 1st Plug set @ 850' with 70 sx.
- 2nd Plug set @ 200' with 20 sx.
- 3rd Plug set @ 240' with 10 sx.

Plug was down @ 10:45 a.m. on June 21, 1976.

State Plugger: Gilbert Balthazor, Paleo, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

06-24-76
JUN 24 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet) 6-24-76


Name of Plugging Contractor Abercrombie Drilling, Inc.
801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Jerry A. Langrher, Exec. V. P.

(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrher
801 Union Center, Wichita, KS 67202

22nd day of June 1976 (Address) 76



Sworn to before me this July 21, 1979

Sandra Richman Notary Public.

CONTRACTOR'S WELL LOG

15-039-20338-00-00

OPERATOR: Baird Oil Company, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: ANTHONY #2
 LOCATION: NW SE Section 16-1S-26W
 Decatur County, Kansas
 GEOLOGIST: Steve Powell
 SPUD DATE: June 14, 1976
 COMPLETION DATE: June 21, 1976

0	60	Sand
60	90	Sand & Shale
90	211	Shale
211	532	Shale & Sand
532	1521	Shale
1521	1625	Sand
1625	1849	Shale
1849	1877	Anhydrite
1877	2235	Shale & Sand
2235	2736	Lime & Shale
2736	2889	Shale & Lime
3889	3165	Lime & Shale
3165	3465	Lime
	3465	Rotary Total Depth

Drilled 211' of 12 1/4" hole. Set 8 5/8" surface @ 211 K.B. with 160 sacks cement. 2% gel. 3% ca.cl. Cement circulated. Plug was down @ 10:15 p.m. June 14, 1976.

Preparing to lay down drill pipe and plug. 1st plug @ 850' w/70 sx. 2nd plug @ 200' w/20 sx. 3rd plug @ 40' with 10 sx. Plug was down @ 10:45 a.m. on June 21, 1976. State Plugger: Gilbert Balthazor, Paleo, Kansas.

RECEIVED
 CONSERVATION DIVISION

SAMPLE TOPS:

Anhydrite 1849 (+539)
 B/Anhydrite 1877 (+511)

JUN 24 1976
 6-24-1976
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)) SS
 COUNTY OF SEDGWICK)


Jerry A. Langrehr-Exec. Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Anthony #2, NW SE Section 16-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 21st day of June, 1976.

Sandra Richman
 Sandra Richman - Notary Public



My Commission Expires: July 21, 1979.