

13-039-20145-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Decatur SEC. 17 TWP. 1S RGE. 26W E/W
 Location as in quarters or footage from lines:

C-SE-NE

Lease Owner Kelso Casing Pulling
 Lease Name Huff #1 Well No. _____
 Office Address Box 176 Chase, Kansas 67524
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 11-20-81
 Plugging completed 11-25-81
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3412'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	252'	none
				4-1/2"	3275'	1000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3150' and set 4 sacks cement. Shot pipe @1997', 1515', 1390' and 1000'. Pulled a total of 31 joints of pipe. Plugged well with 2 sacks hulls, 10 sacks gel, 8-5/8" plug, 120 sacks 50/50 pos, 2% gel, 3% cc. Plugging Completed.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC - 9 1981
 12-9-1981
 CONSERVATION DIVISION
 Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 81

My Commission expires:



Irene Hoover
 Notary Public.