

15-039-20200-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Decatur County, Sec. 17 Twp. 1S Rge. (E) 26 (W)

Location as "NE/CNW%SW%" or footage from lines C NE SE
Lease Owner Rosen Oil Corporation
Lease Name Huff "E" Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 5, 1970
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced December 5, 1970
Plugging completed December 5, 1970
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols of Morland
Producing formation Depth to top Bottom Total Depth of Well 3403 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	276'	8-5/8"	276'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1075 Feet,
Plug and 100 sax Cement; Mud to 310 Feet,
Plug and 25 sax Cement; Mud to 40 Feet,
1/2 sax Halls, Plug bridged w/Kelly and
10 sax Cement to Base of Cellar; 2 sax
Cement in Rat Hole. Job completed @
5 P.M.

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas

12-8-1970


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oilwell Cementing, Inc.
Address Box 169, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
500 Bitting Building, Wichita, Kansas (Address)

Subscribed and sworn to before me this 7th day of December 1970

[Signature] Louise K. Whitted
Louise K. Whitted Notary Public.



My commission expires November 26, 1974.

15-039-20200-00-00

DRILLERS LOG

HUFF "E" NO. 1

CASING RECORD:	OPERATOR: Rosen Oil Corporation	DESCRIPTION:
8-5/8" @ 276' w/200 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	C NE SE Sec. 17-1S-26W Decatur Co., Kans.
TOTAL DEPTH: 3403'	COMMENCED: November 30, 1970	ELEVATION: 2407KB
	COMPLETED: December 5, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	60	
Shale	60	100	
Sand & Shale	100	280	
Shale	280	403	
Shale & Sand	403	1525	
Sand	1525	1611	
Shale & Shells	1611	1867	
Anhydrite	1867	1897	
Shale & Shells	1897	1933	
Shale & Lime	1933	2535	
Lime & Shale	2535	3285	
Lime	3285	3380	
Lime & Shale	3380	3403	D&A

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas
12-8-1970

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 7th day of December, 1970.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1974.