

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD 15-039-20560-00-00

Give All Information Completely  
 Make Required Affidavit

COUNTY Decatur SEC. 4 TWP. 1-S RGE. 26 W  
 Location as in quarters or footage from lines:  
C/NW/NE

NW		•	NE
SW			SE

Lease Owner Cherokee Petroleum Corp.  
 Lease Name Summer Well No. 1  
 Office Address 410 17th, Suite 2300, Denver, CO 80202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed April 23, 1981  
 Application for plugging filed June 30, 1982  
 Plugging commenced July 30, 1982  
 Plugging completed August 6, 1982  
 Reason for abandonment of well or producing formation The well ce  
ceased to produce hydrocarbons in paying quantities.  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Locate Well  
 correctly on above  
 Section Platt.

Name of Conservation Agent who supervised plugging of this well Carl Goodrow  
 Producing formation LKC Depth to top 3308' bottom 3522' T.D. 3623'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
A zone	Oil/ H2O	3308'	3320	8 5/8"	290'	
B zone	Oil/ H2O	3350'	3360'	4 1/2"	3602'	759.25'
C zone	Oil/ H2O	3390'	3410'			
D zone	Oil/ H2O	3423'	3438'			
see reverse side						

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set. Dumped 5 scks. cement on July 30, 1982, sd. at 3200',  
4 scks. hulls, 28 scks. gel, 70 scks. cement, 12 scks gel, 60 scks. cement, set 8 5/8"  
plug, 10 scks. cement 50/50 pos 4% gel, 3% cc.

RECEIVED  
 STATE CORPORATION COMMISSION  
8-18-82  
 AUG 18 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Sun Oil Cementing Company and Oil Field Service and Supply, Inc.


STATE OF Kansas COUNTY OF Decatur, ss.  
James R. Betts, Operator (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James R. Betts  
James R. Betts, President  
 (Address)  
 P.O. Drawer 298, Oberlin, KS 67749

SUBSCRIBED AND SWORN TO before me this 16th day of August, 1982

Rhonda Salem  
 Rhonda Salem Notary Public.

My Commission expires: December 4, 1985



OIL, GAS OR WATER RECORDS

E zone Oil/ H2O 3464-72'  
F zone Oil/H2O 3490-3502'  
G zone Oil/H2O 3510-22'

100 100 100 100  
100 100 100 100  
100 100 100 100  
100 100 100 100