

15-039-20230-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Decatur County, Sec. 4 Twp. 1 Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines NW SE  
Lease Owner A. L. Abercrombie, Inc.  
Lease Name SUMNER "C" Well No. 2  
Office Address 801 Union Center, Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 28, 1972  
Application for plugging filed (verbally) March 28, 1972  
Application for plugging approved (verbally) March 28, 1972  
Plugging commenced March 28, 1972  
Plugging completed March 28, 1972  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation Depth to top Bottom Total Depth of Well 3605 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug was set at 1125' w/110 sx.  
2nd plug was set at 250' w/30 sx.  
Top plug was set at 40' w/10 sx.  
Job completed at 11:00 a.m. 3-28-72.

RECEIVED  
3-30-1972  
STATE CORPORATION COMMISSION  
MAR 30 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1972

My commission expires February 10, 1975

Beverly Mann  
Beverly Mann Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: A. L. Abercrombie, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: SUMNER "C" #2  
 LOCATION: NW SE, Sec. 4-1S-26W  
 Decatur County, Kansas  
 GEOLOGIST: Jack K. Wharton  
 SPUD DATE: March 22, 1972  
 COMPLETION DATE: March 28, 1972

0	105	Clay and Sand
105	131	Flint
131	1025	Shale
1025	1145	Sand
1145	1383	Shale w/Sand Streaks
1383	1485	Sand
1485	1677	Shale
1677	1730	Bentonite
1730	1979	Shale & Shells
1979	2009	Anhydrite
2009	2180	Shale
2180	2570	Shale & Lime
2570	3225	Lime & Shale
3225	3525	Lime
3525	3585	Shale & Lime
3585	3605	Shale & Granite Wash
	3605	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 30 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 3-30-72

Drilled 216' of 12½" surface hole. Set 8-5/8" surface csg. at 206' w/110 sx. on bottom and 40 sx. on top. Cement circulated. Plug was down at 6:30 a.m. 3-22-72. Dry and Abandoned

<u>SAMPLE TOPS</u>		<u>ELEVATION</u>
Anhydrite	1979 (+ 535)	2514 K.B.
B/Anhydrite	2009 (+ 505)	2512 D.F.
Heebner	3251 (- 737)	2506 G.L.
Toronto	3285 (- 771)	
Lansing	3290 (- 776)	
B/K.C.	3502 (- 988)	
Granite Wash	3588 (-1074)	

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SUMNER "C" #2, NW SE, Section 4-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.  
 By: Jerry A. Langrehr  
 Jerry A. Langrehr  
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 29th day of March, 1972.

Beverly Mann  
 Beverly Mann, Notary Public

My Commission Expires:  
 February 10, 1975