


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-147-19051-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec. 36 Twp. 1 Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines NE SE SE  
Lease Owner Petroleum Management, Inc.  
Lease Name Essert Well No. 2  
Office Address 1019 Central Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 10-15- 19 50  
Application for plugging filed 10-30- 19 50  
Application for plugging approved 5-22- 19 56  
Plugging commenced 5-29- 19 56  
Plugging completed 5-31- 19 56  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 3-1- 19 56  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty  
Producing formation Lans. K.C. Depth to top 3431 Bottom 3546 Total Depth of Well 3551 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lans. K.C.	Oil	3482	3528	8-5/8"	192'	None
				5-1/2"	3550'	1460'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 3551' to 3540'  
and ran 5 sacks of cement to 3510'. Bailed  
and mudded the hole to 190', set a 10' rock  
bridge and ran 15 sacks of cement to 130'.  
Mudded the hole to 35', set a rock bridge and  
ran 10 sacks of cement to base of cellar.  
Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John W. Rit chey (employee of owner) or (owner or operator) Agent of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1019 Central Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 1956

My commission expires April 23, 1958

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1956

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 36 T. 1 R. 19W  
BOOK PAGE 63 LINE 27

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY L. B. STABLEFORD

SEC. 36 T. 1 R. 19W

FARM Essert NO. 2

LOC. NE SE SE

15-147-19051-00-00

Phillips

TOTAL DEPTH 3550

COUNTY

COMM. 10-24-50

COMP. 10-24-50



SHOT OR TREATED

CONTRACTOR

ISSUED 12-16-50

CASING

8 5/8" 183' cem w/125 sx.  
5 1/2" 3550' cem w/150 sx.

ELEVATION

PRODUCTION 133 bbl. and no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay, rock	75
shale, sand	185
shale, shells	192
shale	860
shale, sand	1300
sand	1560
shale, redbed	1836
anhyd.	1869
shale, shells	2070
shale, lime shells	2410
lime, shale	3455
lime	3495
lime, shale	3550
Total depth	

Tops: Scout	
Heebner	3403
Lansing	3430

10,000 acid.

12/3538-42  
12/3536-40  
12/3524-28  
12/3497-3501  
12/3522-26  
12/3495-99  
12/3482-84

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 36 T. 1 R. 19W  
BOOK PAGE 63 LINE 27