


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-147-00986-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec. 36 Twp. 1 Rge. 19 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. SW SE NE  
Lease Owner Lawrence & Meltzer Oil Company  
Lease Name Brockett Estate Well No. 2  
Office Address Box 414, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 2-11 19.51  
Application for plugging filed 11-19 19.51  
Application for plugging approved 11-19 19.51  
Plugging commenced 5-2 19.52  
Plugging completed 5-6 19.52  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 5-28 19.52  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Kansas City Depth to top 3422 Bottom 3532 Total Depth of Well 3570 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"		1366'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 3500'; dumped 5 sacks cement. Top of cement 3465'. Mudded hole to 240', set rock bridge, dumped 15 sacks cement, top of cement 195' mudded hole to 35', set rock bridge, dumped 10 sacks cement for cap.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1952  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lawrence & Meltzer Oil Company  
Address Box 414, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Lawrence & Meltzer Oil Company (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Lawrence & Meltzer Oil Company

(Signature) By: *L. Lawrence*  
Box 414, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 1952  
*Anne Meltzer*  
Notary Public.

My commission expires 3-30-53 23-5091-s 8-50-10M

PLUGGING  
FILE SEC 36 T 1 R 19 W  
BOOK PAGE 125 LINE 3

15-147-00986-0000

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock


Wichita, Kansas

Company - HONAKER DRIG. CO., INC.  
Farm - Brockett Estate No. 2

SEC. 36 T. 1 R. 19W  
SW SE NE

Total Depth. 3570  
Comm. 1-17-51 Comp. 3-21-51  
Shot or Treated.  
Contractor. Honaker Drlg. Co., Inc.  
Issued. 9-22-51

County. Phillips  
KANSAS



Elevation. 2255

Production. I.P.P. 85 BO & NW

Figures Indicate Bottom of Formations.

surface soil & lime	160
shale & shells	1735
red bed & shale	1811
anhydrite	1859
shale & shells	2210
shale & lime	2410
shale & shells	2456
sand	2484
pyrite & shale	2510
shale & shells	2990
shale & lime	3145
lime	3215
lime & shale	3410
lime	3570
Total Depth	

Scout Tops:	
Siltstone	3276
Heebner	3395
Kansas City	3422

COMPANY TIME WITH DRILL PIPE

1-23-51 Circ. 30 min.

1-24-51 Circ. 1 hr.

COMPANY TIME WITH OUT DRILL PIPE

1-24-51 circ. 8 hrs.

APR 23 1952

60.

15-147-00986-00-00

LAWRENCE & MELTZER OIL CO.  
GREAT BEND, KANS.

DRILLING LOG  
BROCKETT ESTATE #2, SW SE NE Sec.  
36-18-19W, PHILLIPS CO., KANSAS

CONTRACTOR: HONAKER DRILLING CO., INC.  
GREAT BEND, KANS.

COMPLETION: 2/11/51

DEPTHS		
From	TO	
0	160	Surface Soil & Lime
160	242	Shale & Shells
242	1735	Ditto
1735	1811	Red Bed & Shale
1811	1859	Anhydrite
1859	2210	Shale & Shells
2210	2410	Shale & Lime
2410	2456	Shale & Shells
2456	2484	Sand
2484	2510	Pyrite & Shale
2510	2990	Shale & Shells
2990	3145	Shale & Lime
3145	3215	Lime
3215	3410	Lime & Shale
3410	3570	Lime

Oil String Casing: 5 1/2" O.D., 14-lb., 8-R thd., H-40 Seamless,  
Range 2, New, set @ 3569-ft., w/ 175 Sacks Cement.

Surface Casing: 8-5/8" O.D., set @ 242', w/ 150 Sacks Cement,  
Circulated.

PLACING  
FILE SEC 36 T 1 R 19 W  
BOOK PAGE 18 LINE 3

RECEIVED  
STATE CORPORATION COMMISSION

NOV 19 1951  
CONSERVATION DIVISION  
Wichita, Kansas