

15-147-19052-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Phillips County. Sec. 25 Twp. 1 Rge. 19 (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE SW SE
Lease Owner D. G. Hansen
Lease Name Hammond Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19 September 19 51
Application for plugging filed 18 September 19 51
Application for plugging approved 18 September 19 51
Plugging commenced 18 September 19 51
Plugging completed 19 September 19 51
Reason for abandonment of well or producing formation
No commercial production
If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Lansing Depth to top 3446 Bottom 3666 Total Depth of Well 3666 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	270	none
				5 1/2"	3666	2264

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with sand from 3648 to 3435. Set wood plug and dumped 4 sacks of cement at 3435. Filled with mud to 250'. Filled with rock 10' and dumped 15 sacks of cement at 240'. Filled with mud to 35' and 10' of rock. Put 25 sacks cement in and capped.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to D. G. Hansen
Address Logan, Kansas

STATE OF Kansas, COUNTY OF Phillips, ss.
Dane G. Bales (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dane G. Bales

Logan, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of October, 19 51

[Signature]
Notary Public.

My commission expires 11/27/51

22-2625 2-48-15M
PLUGGING
FILE SEC NTLR (196)
BOOK PAGE 110 LINE 4

DRILLERS LOG

Operator: D. G. Hansen
 Lease: Hammond #1
 Contractor: Honaker Drilling Co., Inc.

15-147-19052-06-00

	From	To
Shale & Shells	0	190
Sand	190	210
Shale & Shells	210	271

Run 9 joints (270.49') 8-5/8" 8rd thd 2 1/4# new casing.
 Cemented w/150 sacks cement, 3 sacks Cacl.

	Shale & Shells	271	1020	
	Shale	1020	1240	
	Sand	1240	1280	
C	Shale & Shells	1280	1700	
	Red Bed & Shale	1700	1810	
O	Anhydrite	1810	1856	
	Shale, Shells,			
P	Pyrite	1856	2060	
	Shale & Shells	2060	2330	
Y	Pyrite & Shale	2330	2459	
	Lime & Shale	2459	3120	
	Lime	3120	3370	
	Lime & Shale	3370	3430	
	Lime	3430	3666	T. D.

Run 3666' new 5 1/2" 1 1/4# 8rd thd casing, set at 3665'
 w/150 sacks cement.

The foregoing is correct to the best of my knowledge.

HONAKER DRILLING CO., INC.

BY Joe J. Honaker (signed)
 President

