

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,848 -00-00

LEASE NAME Huff 'B'

WELL NUMBER 12

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 8 TWP. 1S RGE. 26 (E/W) (W)

COUNTY Decatur

Date Well Completed 4/25/89

Plugging Commenced 4/25/89

Plugging Completed 4/25/89

LEASE OPERATOR DCF Exploration #4
ADDRESS 940 Wadsworth Blve., Ste. 100, Lakewood, CO 80215
PHONE#(303) -693-5234 OPERATORS LICENSE NO. 4964

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-25-89 (date)
by Ed Shumaker (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3584'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put in	Pulled out
			8-5/8"	215'	-0-

RECEIVED
STATE CORPORATION COMMISSION
5-3-1989
MAY 3 1989
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method, materials used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3584'-1950' 10 sks cement @ 40'
20 sks cement @ 1950' 15 sks in rathole
100 sks cement @ 1300'
40 sks cement @ 260'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kelly P. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) Kelly P. Branum

P.O. Box 506, russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 89

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission Expires: February 6, 1992



15-039-20848-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: DCF Exploration
940 Wadsworth Blvd., Ste. 100
Lakewood, Colorado 80215

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Huff 'B' WELL #12

LOCATION: C NE SW
Section 8-1S-26W
Decatur County, Kansas

LOGGERS TOTAL DEPTH: 3580'

ROTARY TOTAL DEPTH: 3584'

COMMENCED: 4/19/89

CASING: 8-5/8" @ 215 w/150 sks cement

ELEVATION: 2478' K.B.

COMPLETED: 4/25/89

STATUS: Dry Hole

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1989
5-3-1989
CONSERVATION DIVISION
WICHITA, KANSAS


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Clay	120'	Top of Topeka	3094'
Shale	950'	Top of Heebner	3206'
Dakota Sand	1200'	Top of Lansing-Kansas City	3250'
Red Bed	1617'	Base of Lansing-Kansas City	3465'
Cedar Hills	1720'	Conglomerate	3554'
Shale	2200'	R.T.D.	3584'
Shale & Lime Stks.	3093'		


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kelly P. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kelly P. Branum

Subscribed and sworn to before me on April 27, 1989.

My commission expires: February 6, 1992.


GLENDA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92


Glenda R. Tiffin, Notary Public