


15-147-00114-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec. 30 Twp. 18 Rge. 18W (E) (W)  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SW-SW-SW  
Lease Owner Lawrence & Meltzer Oil Company  
Lease Name Brockett Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 10-18-52 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed \_\_\_\_\_ 10-22-52 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3540 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"		571'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from 3540' to 3500' and ran 4 sacks of cement. Mudded hole to 235' set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35' and ran 10 sacks of cement. Plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 29 1952

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence & Meltzer Oil Co.  
By Lawrence  
(Address)

SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_

My commission expires \_\_\_\_\_

Notary Public.

PLUGGING  
FILE SEC 307 1 R 1824  
BOOK PAGE 52 LINE 31

15-147-00114-00-00  
September 15, 1952

Donaker Drilling Company  
#1 Helen Brockett  
SW 3/4 SW Section 30-15-18W  
Phillips County, Kansas

Elevation: 2217' (Rotary Bushing)  
Corrected

8-5/8" surface casing set at 225' and cemented w/125 sacks cement and 2 sacks calcium chloride.

Top Ankerite 132  
Top Siltstone 3279  
Top Hoehner 3396  
Top Kansas City 3421 (-1174)

C  
O  
P  
Y

- 3472 - 75 Limestone white, finely crystalline, partly fossiliferous, trace poor porosity, light saturation. No odor.
- 3489 - 93 Limestone cream, finely crystalline, poor to fair porosity, fair saturation. Show free oil in wet sample. No odor.
- 3493 - 102 Limestone white, finely crystalline, fossiliferous, poor to fair porosity, light to fair saturation. No. odor.
- 3506 - 10 Limestone as above, poor to fair porosity, fair saturation. Show free oil in wet sample. Paint odor.
- 3511 - 18 Limestone white, finely crystalline, fossiliferous and partly shaly, 30% fair porosity, fair saturation. Show free oil in wet sample.
- 3521 - 31 Limestone cream, finely crystalline, partly fossiliferous, fair to good porosity and good saturation. Good show free oil in wet sample. Good odor.

Total Depth Rotary 3540'

8" casing set and cemented at 3539' w/175 sacks.

WILLIAMS-NEWILLIAMS GEOLOGICAL SERVICE

By Jim B. Newilliams

**PLUGGING**  
FILE SEC 30 1 182  
BOOK PAGE 52 LINE 31

RECEIVED  
STATE CORPORATION COMMISSION

OCT 17 1952  
CONSERVATION DIVISION  
Wichita, Kansas