

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22013-00-00
Spot: NWNE Sec/Twnshp/Rge: 16-6S-22W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: RUSH ESTATE UNIT D Well #: 3
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 221 S. BROADWAY, SUITE 302
WICHITA, KS 67202

PKR Size: 4.5 feet: 3849 525 SX CMT
SURF Size: 8.625 feet: 259 185 SX CMT

512513

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2004 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY WAGNER Company: ANDERSON ENERGY, INC. Phone: (785) 735-4270

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1448' set with 400 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2004 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.
Swaged onto 4 1/2" - mixed and pumped 175 sxs cement with 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3758	3761		

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 4-1-04

INV. NO. 2004061366

Form CP-2/3

MAR 30 2004

ENERGY PRODUCTION, INC.
1100 BITTING BLDG.
WICHITA, KS. 67202

REPLACEMENT CARD

#3 'D' RUSH

16-6-22W
C NW NE

CONTR ABERCROMBIE DRILLING CITY GRAHAM
GEOL ED DONNELLY FIELD HOUSTON SOUTH

ELV 2370 KB SPD 6/29/84 CARD ISSUED 8/30/84 IP P 18 BOPD, NW
2365 GL DRLG COMP 7/4/84 LKC 3758-3761
API 15-065-22.013



LOG	Tops	Depth/Datum	
ANH	2019+ 351	8 5/8 " 259 / 185SX, 4 1/2 " 3849 / 525SX
TOP	3373-1003	DST (1) 3582-3613 (HEEB, TOR) / 30-45-60-75, REC 82' MW (CHL 15,000 PPM), 186' WM, SIP 1207-1172#, FP 46-56 / 92-150#, BHT 112°
HEEB	3575-1205	DST (2) 3750-66 (LKC) / 30-45-60-75, REC 62' CL OIL, 62' MCO (70% M, 30% OIL), OIL REC .6B / 90", SIP 266-255#, FP 35-46 / 46-46#, BHT 114°
TOR	3601-1231	DST (3) 3765-83 (LKC) / 30-45-30-45, (1ST OP) WB, DIED / 14", REC 5' OIL SPKD M, PRESSURES NA
LANS	3618-1248	MICT - CO, PF (LKC) 3758-61, W / 3 SPF, AC 250G (15% INT) & 1250G (15% NE), SWB DWN, SO, SET 2 3/8 " TBG AT 3780', POP, P 18 BOPD, NW (GR 38°), 7/26/84
PBTD	3775-1405	
RTD	3850-1480	

INFO RELEASED: 9/12/85 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

15303027