

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00745-00-00
Spot: SENE Sec/Twnshp/Rge: 22-20S-19W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: HOLMAN Well #: 2
County: PAWNEE Total Vertical Depth: 4300 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 4.5 feet: 4299 WITH 125 SX CMT
SURF Size: 8.625 feet: 342 WITH 200 SX CMT

#139⁷⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2004 5:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: SAND TO 4180' & 4 SX CMT. PUMP 100 SX CMT WITH 500# HULLS. PRESSURE TEST. PERFORATE & PUMP 75 SX CMT. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2004 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND TO 4180' WITH 4 SX CMT. PUMPED 100 SX CMT WITH 500# HULLS TO 3200'. PRESSURED TO 650# AND SHUT IN WITH 500# AND HELD. THE 100 SX CMT COVERED FROM 1200' TO 3200'. 03/18/04: PERFORATED AT 500'. PUMPED 75 SX CMT. PRESSURED TO 1100#. SHUT IN WITH 950#. TIED ONTO BACKSIDE & PUMPED 75 SX CMT. PRESSURED TO 500# AND HELD.

Perfs:

Top	Bot	Thru	Comments
4251	4262		

RECEIVED
MAR 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR 22 2004
KCC Dodge City

Signed

Michael Maier
(TECHNICIAN)

INVOICED

3-30-04

2004061354

Form CP-2/3