

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21873-00-00
Spot: SWNE Sec/Twnshp/Rge: 16-6S-22W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: RUSH ESTATE UNIT D Well #: 2
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 221 S. BROADWAY, SUITE 302
WICHITA, KS 67202

PROD Size: 4.5 feet: 3849 150 SX CMT
SURF Size: 8.625 feet: 248 185 SX CMT

\$125¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2004 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY WAGNER Company: ANDERSON ENERGY, INC. Phone: (785) 735-4270

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1462' set with 400 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2004 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.
Swaged onto 4 1/2" - mixed and pumped 175 sxs cement with 500# hulls.
Max. P.S.I. 800#. S.I.P. 175#.

Perfs:

Top	Bot	Thru	Comments
3762	3765		

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

10

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 2-1-04
INV. NO. 2004061366

Form CP-2/3

MAR 30 2004

ENERGY PRODUCTION, INC.
320 HARDAGE CENTER
WICHITA, KS 67202

REPLACEMENT CARD

16-6-22W
C SW NE


#2 "D" RUSH

CONTR ABERCROMBIE DRILLING CO. CTY GRAHAM

GEOL _____ FIELD HOUSTON SOUTH

ELV 2372 KB SPD 10/17/83 CARD ISSUED 2/16/84 IP P 30 BOPD, NW
2367 GL LKC 3762-3765

API 15-065-21,873



LOG	Tops	Depth/Datum
ANH		2017+ 355
B/ ANH		2049+ 323
TOP		3401-1029
HEEB		3582-1210
TOR		3608-1236
LANS		3625-1253
MUN CR		3728-1356
BKC		3810-1438
RTD		3850-1478
LTD		3849-1477

API NOT ASSIGNED

.8 5/8 " 248/185SX, 4 1/2 " 3849/150SX
DST (1) 3756-74 (MUN CR) / 30-45-60-90, 300' GIP, REC-93'
GSY OIL, 62' OCM (13.95' G, 106.95' OIL, 34.1' M), SIP 296-
296#, FP 55-66 / 77-88#
MICT - CO, PF (MUN CR) 3762-65, W/ 4 SPE, AC 500G (15%
INS), SWB DWN, SO, SET 2 3/8 " TBG AT 3793, POP, P 30
BOPD, NW 11/8/83

INFO RELEASED: 1/17/85 - WAS OIL WELL - TIGHT HOLE
NOTE: INFO RELEASED 2/16/84 - WAS TIGHT HOLE

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WICHITA, KS
3762-3765