

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21519-00-00

Spot: SE

Sec/Twnshp/Rge: 32-16S-19W

1320 feet from S Section Line, 1320 feet from E Section Line

Lease Name: LITTLER

Well #: 1

County: RUSH

Total Vertical Depth: 3808 feet

Operator License No.: 32500

MSCC Size: feet: 1305 WITH 250 SX CMT

Op Name: T & P OIL & GAS, L.L.C.

PROD Size: 5.5 feet: 3786 WITH 150 SX CMT

Address: 7801 METCALF

SURF Size: 8.625 feet: 370 WITH 165 SX CMT

OVERLAND PARK, KS 66204

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/22/2004 9:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: J.D.DREILING

Company: ALLIED CEMENT COMPANY

Phone: (620) 793-5861

Proposed Plugging Method: PER KCC DODGE CITY OFFICE RECOMMENDATIONS.

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/22/2004 11:03 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3793'. PUMPED DOWN 5 1/2" WITH 500# HULLS - 30 SX CMT - 25 SX GEL - 150 SX CMT. MAXIMUM PRESSURE 2700 PSIG. INITIAL SHUT IN PRESSURE 1300 PSIG. PUMPED 5 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 600 PSIG.

Perfs:


Top	Bot	Thru	Comments
3786	3793	OH	

RECEIVED  
MAR 30 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Richard M. Lacey*

(TECHNICIAN)

INVOICED

DATE 3.30.04

INV. NO. 2004061360

Form CS 1/03