

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20719-00-01
Spot: E2SESE Sec/Twnshp/Rge: 10-35S-20W
1270 feet from S Section Line, 510 feet from E Section Line
Lease Name: BOX RANCH Well #: B 2
County: COMANCHE Total Vertical Depth: 5640 feet

Operator License No.: 4145
Op Name: ROBERTS AND MURPHY, INC.
Address: PO BOX 7125 1500 N. MARKET
SHREVEPORT, LA 71137

CIBP Size: feet: 5316 WITH 2 SX CMT
PROD Size: 4.5 feet: 5475 WITH 200 SX CMT
SURF Size: 8.625 feet: 639 WITH 350 SX CMT

183³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2004 1:15 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: BOB MOOREHEAD Company: ROBERT & MURPHY Phone: (318) 221-8601

Proposed Plugging Method: SET CIBP @ 5300' & 2 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2004 3:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5475'. SET CIBP @ 5316' WITH 2 SX CMT ON TOP. 1ST PLUG RAN TUBING TO 900' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TUBING TO 650' & SPOT 50 SX CMT. 3RD PLUG PULL TO 320' & CIRCULATE 85 SX CMT TO SURFACE. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5403	5418		
5393	5397		

RECEIVED
MAR 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 2700' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed _____

(TECHNICIAN)

INVOICED

DATE 3.30.04

INV. NO. 2004061359

Form CP 2/3