

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23174-00-00  
Spot: NENE Sec/Twnshp/Rge: 14-20S-22W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: MAIER Well #: 3  
County: NESS Total Vertical Depth: 4962 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 155 N. MARKET, STE. 1020  
WICHITA, KS 67202

MSSC Size: feet: 1485 WITH 275 SX CMT  
PROD Size: 5.5 feet: 4750 WITH 175 SX CMT  
SURF Size: 8.625 feet: 620 WITH 250 SX CMT

#161 27

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2004 3:30 PM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC  
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: 1ST PLUG PUMP 200# HULLS & 30 SX CMT AT 4300'. DISPLACE WITH GET TO 1485'. CMT TO SURFACE FROM 1485'.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/22/2004 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4754'. PUMPED 200# HULLS & 30 SX CMT. MIX 10 SX GEL WITH 24 BBL WATER. PRESSURE TO 2000# AND SHUT OFF. RAN TUBING TO 1000' & CIRCULATE TO SURFACE WITH 80 SX CMT. PULLED TUBING AND TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# AND HELD.

Perfs:

Top	Bot	Thru	Comments
4394	4397		

RECEIVED  
MAR 30 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
MAR 23 2004  
KCC Dodge City

Signed

*Michael Maier*  
(TECHNICIAN)

INVOICED  
DATE: 3.30.04  
WV. NO. 2004061355

Form C-27