

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22866-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 29-15S-11W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CHEGWIDDEN Well #: 5
County: RUSSELL Total Vertical Depth: 3422 feet

Operator License No.: 6902
Op Name: BORELL, ALBERT W.
Address: PO BOX 158
WILSON, KS 67490

PROD Size: 5.5 feet: 3421 w/125 sxs cmt
SURF Size: 8.625 feet: 513 w/250 sxs cmt

#111 22

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2004 9:00 AM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: BILL SEIFERS Company: ALBERT BORELL OIL COMPANY Phone: (785) 658-2594

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2004 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Swaged onto 5 1/2" - mixed and pumped 240 sxs cement with 500# hulls.
Max. P.S.I. 1800#. S.I.P. 1100#.
Hooked up to the annulus and pumped 25 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

10

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE . 4-1-04
INV. NO. 2004061367

Form CP-2/3

MAR 29 2004

ALBERT W. BORELL
WILSON, KS 67490

INVOICE

29-15 - 11W
SW SW SW

site: 4-3/4 N & 5 E OF BEAVER, KS

conr: RED TIGER DRILLING COMPANY

sq: RUSSELL
field: DAVIDSON

API 15-187-22866

ganh: JAMES SCHMIDT

if	spd	drig	carc	last
date 09/18/89	date 09/18/89	comp 09/27/89	issued 12/13/89	revised 12/13/89

ELW 1860 KB LOG

tops.....	depth/datum
HOW.....	2571 -711
TOP.....	2608 -748
QH.....	2809 -849
HEEB.....	2900 -1040
IATAN.....	2992 -1132
LANS.....	3007 -1147
BKC.....	3270 -1410
CONG.....	3308 -1448
ARE.....	3338 -1478
RTD.....	3422 -1562

IP status:
OIL, P 10 BO & 50 BWPD & TR GAS, ARB 3340-3348,
CSG: 8-5/8" 513 / 250 SX, 5-1/2" 3421 / 125 SX
NO CORES
DST (1) 2928-2850 (SHAW), / TIMES NA, WB & INCRG,
180' GIP, REC 120' GSY SLI OCM, NO IFF ISIP 784#
FSIP 367# FFP 91# -100# IHP 1524# FHP 1517#
DST (2) 3007-3050 (LANS), / TIMES NA, SB, 600' GIP,
REC 240' GSY WTRY M ISIP 1380# FSIP 1356# IFF
73# -89# FFP 114# -138# IHP 1685# FHP 1671#
DST (3) 3182-3188 (LKC), / TIMES NA, WB STDY BLO,
REC 30' WM, W / OIL SPKS ISIP 431# FSIP 187# IFF
24# -24# FFP 32# -32# IHP 1776# FHP 1759#

ALBERT W. BORELL
WILSON, KS 67490

#5 CHEGWIDDEN

29-15 - 11W
SW SW SW

DST (4) 3338-3343 (ARB), / TIMES NA, GB THRU-OUT, 30' GIP, REC 750' FREE GSY OIL, 150'
MDY GSY OIL, 30' W ISIP 1119# FSIP 1111# IFF 61# -252# FFP 285# -350# IHP 1892# FHP
1881#
DST (5) INTV NA (ARB), MISRUN
DST (6) 3344-3355 (ARB), / TIMES NA, SB, REC 2600' SULPHUR WTR ISIP 1119# FSIP 1111#
IFF 333# -980# FFP 1062# -1108# IHP 1884# FHP 1871#
MICT - CO, PF (ARB) 3340-3346, W / 4 SPF, AC 250 GAL (15%), SO, SET 2-1/2" TBG AT 3397,
NO PKR, POP, P 10 BO & 50 BWPD & TR GAS, 10/15/89

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

Log	Depth/Datum
SC	1104 + 861
B/SC	1137 + 828
TOP	2978-1013
HEEB	3206-1241
TOR	3226-1261
LANS	3255-1290
BKC	3484-1519
PENN CONG	3523-1558
ARB	3557-1592
RTD	3565-1600

AP1 15-051-23,735
 8 5/8 " 214.4 / 2 " 3559
 MICT - CO TO 3565, (ARB OH), SWB DWN, SO, AC 500G (NON-
 E), ONFU 1365 FL, SWB DWN & REC 3 80 / 15 HRS, SET GIBP
 AT 3470, PF (LKC) 3452-56, W / 2 SPS, AC 1500G (28%), SWB
 DWN & REC 4 BFP (50% OIL) / 2 HRS, SET GIBP AT 3365, PF
 (LKC) 1 / 3283, 1 / 3325, 1 / 3353, AC 3000G (18%), SWB DWN,
 REC 13 BOPH / 4 HRS, DRLD PLUG TO 3470, POP, P 120 BOPD,
 NW, 2/22/84

R. F. NIXON OPERATIONS
 207 W. 12TH STREET
 HAYS, KS 67601

CONTR # JAY-LAN CORPORATION
 CITY ELLIS

GEOL FIELD DEGENHART SE

ELV 1955 KG SPD 1/5/84
 CARD ISSUED 4/5/84
 #1 TIEDEMAN
 23-15-17W
 SW SM NW

+	+	+
+	+	+
+	+	+

LKC 3283-3455 OA
 P 120 BOPD, NW