

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23735-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 23-15S-17W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: TIEDEMAN Well #: 1
County: ELLIS Total Vertical Depth: 3565 feet

Operator License No.: 30598
Op Name: HASELHORST, IRVIN E. DBA HABIT PE
Address: 639 280TH AVE
HAYS, KS 67601

PROD Size: 4.5 feet: 3559 w/125 sxs cmt
SURF Size: 8.625 feet: 214 w/135 sxs cmt

115-86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2004 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: IRVIN HASELHORST Company: HABIT PETROLEUM Phone: (785) 625-6190

Proposed Plugging Method: Ordered 200 sxs cement and 500# hulls.
Plug with tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2004 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

8 5/8" S.P. at 214' w/135 sxs cement.
4 1/2" casing at 3559' w/125 sxs cement.
DV at 1107' w/325 sxs cement.
Ran tubing to 3200' - spotted 100 sxs cement with 300# hulls.
Pulled tubing to 1200' - circulated with 60 sxs cement with 200# hulls.
Pulled all tubing and squeezed 4 1/2" casing with 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Tied to 4 1/2" x 8 5/8" annulus and squeezed 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 0#.
Total of 200 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. AMERICAN TANK SERVICE-WATER.

Plugged through: TBG

District: 04

HP.

Signed Roger L. Moses
(TECHNICIAN)

INVOICED

DATE 4-1-04

INV. NO. 2004061370

MAR 29 2004

R. P. NIXON OPERATIONS
 207 W. 12TH STREET
 HAYS, KS 67601

#1 TIEDEMAN

23-15-17W
 SW SW NW

CONTR JAY-LAN CORPORATION

CTY ELLIS

GEOLOGICAL

FIELD DEGENHART SE

ELV 1965 KE SPD 1/5/84 CARD ISSUED 4/5/84 IP P 120 BOPD, NW
LKC 3283-3456 OA

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth/Datum
SC	1104+	861
B/SC	1137+	828
TOP	2978	1013
HEEB	3206	1241
TOR	3226	1261
LANS	3255	1290
BKC	3464	1519
PENN CONG	3523	1558
ARB	3557	1592
RTD	3565	1600

API 15-051-23,735

8 5/8 " 214; 4 1/2 " 3559
 MICT - CO TO 3565, (ARB OH), SWB DWN, SO, AC 500G (NON-
 E), ONFU 1365' FL, SWB DWN & REC 5 BO / 15 HRS, SET CIBP
 AT 3470, PF (LKC) 3452-56, W / 2 SP, AC 1500G (28%), SWB
 DWN & REC 4 BFP (50% OIL) / 2 HRS, SET CIBP AT 3365, PF
 (LKC) 1 / 3283, 1 / 3325, 1 / 3353, AC 3000G (18%), SWB DWN,
 REC 13 BOPH / 4 HRS, DRLD PLUG TO 3470, POP, P 120 BOPD,
 NW, 2/22/84

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS