

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20183-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 19-14S-14W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: MILBERGER Well #: 2  
County: RUSSELL Total Vertical Depth: 3312 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

PROD Size: 5.5 feet: 3310  
SURF Size: 8.625 feet: 242 w/175 sxs cmt

Well Type: SWD UIC Docket No: D19091.0 Date/Time to Plug: 03/24/2004 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/24/2004 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 475' - 875' - 1525'.  
TIH with tubing to 2200' - mixed and circulated 200 sxs cement with 500# hulls.  
POOH. Topped with 30 sxs cement.  
Max. P.S.I. 800#. S.I.P. 300#.  
Annulus full of cement.

RECEIVED  
APR 02 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

Form CP-2/3

APR 01 2004

MARION OIL CO.  
528 S. 5TH ST.  
RUSSELL, FS.

SWD  
#2 MILBERGER "OWWD"

19-14-14W  
NW SW NW

CONTRACT EMPHASIS OIL OPERATIONS CO. RUSSELL

FIELD GORHAM

LOG NO. 448 AR. 4/13/78 CARD. ISSUED 3/3/77 IP D&A/ARB

+	+	+
+	+	+
+	+	+

API 15-167-20, 183-A

LOG	TOPS	DEPTH	DATUM
ANH		860	+ 979
B ANH		906	+ 942
TARK		2872	= 624
TOP		2732	= 884
HEEB		2957	= 1109
TOR		2976	= 1128
LANS		3017	= 1169
B&C		3218	= 1370
ARB		3228	= 1380
RTD		3272	= 1424
LTR		3272	= 1424
L. T.		3312	= 1464

OLD INFO: OPERATOR WAS DEAN-CLARK, IN  
#1 NAT; SPD 3/31/68, SET 8-5/8" 248/  
175SX; COMPLETED AS D&A/ARB 4/11/68  
DST (1) 2903-35/1', REC 35' M, SIP 18'  
712#/30", FP 8-41#  
DST (2) 3020-60/2', REC 60' GIP, 180'  
GCWM W/F50, SIP 365-305#, FP 45-  
110#

NEW INFO: CO & UD 3312', SET 5 1/2"  
3310, MFCT - CO TD, PF (ARB) INTERVAL  
NA, NON-COMMERCIAL - CONVERT TO SWI#?  
LATER:

INDEPENDENT OIL & GAS SERVICE  
WILLIAM MANTON