

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02648-00-00
Spot: SENENE Sec/Twnshp/Rge: 31-13S-16W
4290 feet from S Section Line, 300 feet from E Section Line
Lease Name: BRUNGARDT Well #: 2
County: ELLIS Total Vertical Depth: 3440 feet

Operator License No.: 30420
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR
Address: 30-38 48TH STREET
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3435 150 SX CMT
SURF Size: 8.625 feet: 217 160 SX CMT

#111⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2004 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: VINCE WERTH Company: V.J.I. NATURAL RESOURCES Phone: (785) 625-8360

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well squeezed at 540' w/250 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2750' - mixed and pumped w/100 sxs cement with 300# hulls.
Pulled up to 1400' and circulated 130 sxs cement with 200# hulls.
POOH. Topped with 50 sxs cement.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to the annulus and pumped 10 sxs cement.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3284	3287		
3265	3271		
3257	3260		
3183	3187		

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 4-1-04
INV. NO. 2004061371

MAR 23 2004

31-13-16W

ARTNEIL CO. & OAK FLEMING #2 BRUNGARDT APP SE NE NE

Contr. PRIME DRLG ELLIS County

E. 1930 Comm. Comp. 10-26-56 IP 25 BOPD

Tops	Depth	Datum	Casing
ANH	1046	884	8" 217
			5" 3435
HEEB	3132	-1202	DST 3171-92/1 HR, 360' G, 32" HO & GCM
TOR	3153	-1223	60' WCM, BHP 295#
LANS	3180	-1250	DST 3199-17/1 HR, 350' GSY 0, 120' MDY 0
			40" V HO & GCM, BHP 450#
			DST 3353-77/1 HR, 8' M, BHP 0#
			PERF 20/3209-14: BAIL 25' 60/1 HR: ACID
			2,500: SWB 20' BO, NW 3/3 HRS
ARB	3434	-1504	
TD	3440	-1510	

HERZOG POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NOV 27 1956