

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02647-00-00  
Spot: NESENE Sec/Twnshp/Rge: 31-13S-16W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BRUNGARDT Well #: 1  
County: ELLIS Total Vertical Depth: 3485 feet

Operator License No.: 30420  
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR  
Address: 30-38 48TH STREET  
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3466 w/150 sxs cmt  
SURF Size: 8.625 feet: 204 w/145 sxs cmt

#113<sup>26</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2004 1:30 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: VINCE WERTH Company: V.J.I. NATURAL RESOURCES, INC. Phone: (785) 625-8360

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Well DV'd 1094'w/500 sxs.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 03/26/2004 4:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

T.I.H. with tubing to 2750' w/100 sxs cement with 300# hulls.  
Pulled up to 1375' - pumped 85 sxs cement and 200# hulls with cement circulating.  
POOH. Tied onto 5 1/2" casing and pumped 115 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 500#.  
Hooked up to annulus - backside full.

Perfs:

Top	Bot	Thru	Comments
3260	3264		
3245	3248		
3214	3222		

RECEIVED  
MAR 31 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Ed Schumacher  
(TECHNICIAN)

INVOICED  
DATE 4-1-04

INV. NO. 2004061371

Form CP-2/3

MAR 29 2004

ARTNELL &amp; OAK FLEMING

#1 BRUNGARDT

31-13-16W  
NE SE NE

Contr. PRIME DRILLING

ELLIS

County

E-1961RB

Comm.

Comp.

2-17-56

IP

296 BOPD/LANS

Tops	Depth	Datum
ANH	1080	881
LANS	3210	-1249
ARB	3464	-1503
TD	3485	-1524

Casing  
 8" 204  
 5" 3466  
 DST 3200-20, 180' GC MDY WTR  
 60' O & GCM, 120' OIL, 180'  
 OCW, 240' WTR, BHP 770#  
 DST 3234-48/1 HR, 80' V HO &  
 GCM, 1700' GSY OIL, BHP 800#  
 DST 3254-96, 30' OGM, 255' O  
 & GGSW, BHP 1250#; DST 3464-  
 73, 30' SL OCM, BHP

HERZOG

75#


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS