

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02713-00-00
Spot: S2NENW Sec/Twnshp/Rge: 19-14S-14W
4290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MAI Well #: 3
County: RUSSELL Total Vertical Depth: 3277 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3273
SURF Size: 8.625 feet: 135

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2004 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 450' - 900' - 1600'.
Swaged onto 5 1/2" - mixed and pumped 325 sxs cement with 500# hulls.
Max. P.S.I. 800#. S.I.P. 450#.
Annulus full of cement.

Perfs:

RECEIVED
MAR 31 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

MAR 29 2004

J W BRADEN

#3

MA1

19-14-14W
S2 NE NW

33

Contr. _____ RUSSELL _____ County

E 1860 Comm. _____ Comp. 5-16-52 IP 50 BOPD

Tops	Depth	Datum	Casing
ANH	890	970	8 th 135 PERF 16s 3274-75
			5 th 3273 1 BOPH: ACID 20
TOP	2737	-877	
HEEB	2964	-1104	
LANS	3023	-1163	
ARB	3273	-1413	
TD	3277	-1417	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS