

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,877-00-00

LEASE NAME Whale

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 1 SRGE. 26 (E) or (W)

LEASE OPERATOR Vincent Oil Corporation

COUNTY Decatur

ADDRESS 100 No. Main, Suite 500 Wichita, Kansas 67202-1308

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 11-22-91

Character of Well oil

Plugging Commenced 1-23-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-23-92

The plugging proposal was approved on 1-23-92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation LKC Depth to Top 3274 Bottom 3473 T.D. 3594

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	236	8 5/8"	236	none
LKC	Production	0	3593	4 1/2"	3593	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Rigged up BJ Services. Mixed 200 sx of 65/35 Pozmix cement with 10% gel and 500# of cottonseed hulls. Pumped down casing and pressured to 500# and shut in. Mixed 100 sx of same cement and pumped annulus full. Shut in at 250#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Titan Services License No. _____

Address P.O. Box 27 Oakley, Kansas 67748

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss. _____

Richard A. Hiebsch, Vice President (Employee of Operator) or _____
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch V.P.

(Address) 100 N. Main, Suite 500 Wichita, KS

RECEIVED
STATE CORPORATION COMMISSION
02-04-1992
FFA 03 1009
CONSERVATION DIVISION
WICHITA, KANSAS



AND SWORN TO before me this 4th day of February, 19 92

Julie K. Stout
Julie K. Stout Notary Public

My Commission Expires: July 23, 1993



COMP. DENSITY
COMP. NEUTRON
LOG

COMPANY VINCENT OIL CORPORATION
 WELL #1 WHALE 15-039-20,877-00-00
 FIELD WILDCAT
 COUNTY DECATUR STATE KANSAS
 LOCATION
 C - SE - NW
 3300 FSL - 3300 FEL
 SEC. 20 TWP 1 S RGE 26 W

OTHER SERVICES
DIL/LL3

PERMANENT DATUM GROUND LEVEL ELEV. 2493
 LOG MEASURED FROM K.B. 5 FT. ABOVE PERMANENT DATUM
 DRILLING MEASURED FROM KELLY BUSHING
 ELEV.: K.B. 2498
 D.F. ----
 G.L. 2493

DATE	10-20-91				
RUN NO.	ONE				
DEPTH-DRILLER	3520				
DEPTH-LOGGER	3522				
BTM. LOG INTER.	3499				
TOP LOG INTER.	2900				
CASING-DRILLER	8 5/8 @ 236		@		@
CASING-LOGGER	NOT LOGGED				
BIT SIZE	7 7/8				
FLUID TYPE	CHEMICAL/ MONPAC				
DENS.	9.4	VISC.	44		
PH	10.0	FLUID LOSS	10.0 ML	ML	ML
SOURCE OF SAMPLE	FLOWLINE				
RM @ MEAS. TEMP.	1.4 @ 62	F	@	F	@
RMF @ MEAS. TEMP.	1.0 @ 62	F	@	F	@
RMC @ MEAS. TEMP.	1.7 @ 62	F	@	F	@
SOURCE: RMF/RMC	C	C			
RM @ BHT	.85 @ 106	F	@	F	@
TIME SINCE CIRC.	2 HRS.				
MAX. REC. TEMP.	106 F @ T.D.		F@	F@	F@
EQUIP. LOCATION	#702 LIB.				
RECORDED BY	TOLLEFSON				
WITNESSED BY	MR. DEAN				

RECEIVED
 JAN 21 1992
 CONFESSION DIVISION
 WILDCAT KANSAS
 STATE CORPORATION COMMISSION